

| TITLE: | <u>retainin</u> | NG WALL | | | | | | |
|--|-------------------------|---|---|--|--|--|--|--|
| VERSION: | V2.2 | | | | | | | |
| DATE PUBLISHED: | 06/23/2 | 2 | | | | | | |
| DEFINITION | | | | | | | | |
| DEFINITION: | A vertical | structure that | retains soil or rock at various grades. | | | | | |
| PURPOSE: | To preven | t erosion on sl | oped land or to add usable space. | | | | | |
| COMMON COMPONENTS: | Post; Raili | ng; Block | | | | | | |
| LOCATION: | | Unit | None | | | | | |
| | | Inside | None | | | | | |
| | \boxtimes | Outside | Property grounds | | | | | |
| MORE INFORMATION: For the purpose of this inspection, a "retaining wall" is only classified as such if it is at least 24 inches tall and include decorative planters or foundation wall. | | | | | | | | |
| DEFICIENCY 1: LOCATION: | Retaining wall | etaining wall is leaning away from the fill side. | | | | | | |
| DEFICIENCY 2: LOCATION: | Retaining wall Outside | is partially or | completely collapsed. | | | | | |

DEFICIENCY I — OUTSIDE: RETAINING WALL IS LEANING AWAY FROM THE FILL SIDE.

DEFICIENCY CRITERIA: Retaining wall is leaning away from the fill side.

HEALTH AND SAFETY DETERMINATION: Moderate The Moderate Health and Safety category includes deficiencies that, if evident in the home or

on the property, present a moderate risk of an adverse medical event requiring a healthcare visit; cause temporary harm; or if left untreated, cause or worsen a chronic condition that may have long-lasting adverse health effects; or that the physical security or safety of a resident or

their property could be compromised.

CORRECTION TIMEFRAME:

30 days

HCV PASS / FAIL:

Fail

HCV CORRECTION TIMEFRAME:

30 days

INSPECTION PROCESS:

OBSERVATION: - Look at the retaining wall while standing parallel to determine if the wall is standing upright.

- Verify the wall is not more than 90 degrees from the base of the slope.

REQUEST FOR HELP: - None

ACTION: - Measure the retaining wall to verify the height is 24 inches or greater.

- If it is not at least 24 inches, then it is not subject to inspection.

MORE INFORMATION: - If the retaining wall is leaning (sloped) toward the fill side, do not cite a deficiency.

- If present, inspect the guardrail under the Guardrail standard.

DEFICIENCY 2 — OUTSIDE: RETAINING WALL IS PARTIALLY OR COMPLETELY COLLAPSED.

DEFICIENCY CRITERIA: Retaining wall is partially or completely collapsed.

HEALTH AND SAFETY DETERMINATION: Moderate The Moderate Health and Safety category includes deficiencies that, if evident in the home or

on the property, present a moderate risk of an adverse medical event requiring a healthcare visit; cause temporary harm; or if left untreated, cause or worsen a chronic condition that may have long-lasting adverse health effects; or that the physical security or safety of a resident or

their property could be compromised.

CORRECTION TIMEFRAME:

30 days

HCV PASS / FAIL:

Fail

HCV CORRECTION TIMEFRAME:

30 days

INSPECTION PROCESS:

OBSERVATION: - Look at the entire retaining wall for signs of collapse.

REQUEST FOR HELP: - None

ACTION: - None

MORE INFORMATION: - None



SUMMARY OF CHANGES

TITLE: RETAINING WALL

VERSION: V2.2

DATE PUBLISHED: 06/23/22

| FIELD | Change | Version | Date |
|---------------------------------|--|---------|------------|
| | Abbreviated published version | V2.2 | 2022-06-23 |
| Name Variants | Removed from published version | | |
| Common Materials | Removed from published version | | |
| Rationale | Removed from published version | | |
| Tools or Equipment | Removed from published version | | |
| Deficiency I | | V2.2 | 2022-06-23 |
| Health and Safety Determination | Outside: Relabeled from "Standard" to "Moderate" | | |
| Deficiency 2 | | V2.2 | 2022-06-23 |
| Health and Safety Determination | Outside: Relabeled from "Standard" to "Moderate" | | |
| | Copyedits | V2.1 | 2021-04-02 |
| Deficiency I | | V2.0 | 2020-10-28 |
| Health and Safety Determination | Added standardized description | | |
| HCV Pass / Fail | Field added; response input as "Fail" | | |
| Deficiency 2 | | V2.0 | 2020-10-28 |
| Health and Safety Determination | Added standardized description | | |
| HCV Pass / Fail | Field added; response input as "Fail" | | |
| Overall Formatting | Complete rework of document format and layout | VI.3 | 2020-07-31 |
| Definition | Revised definition | VI.3 | 2020-07-31 |
| Purpose | Field added | VI.3 | 2020-07-31 |
| Common Components | Revised common components | VI.3 | 2020-07-31 |
| More Information | Field added | V1.3 | 2020-07-31 |



| Deficiency I | | Separated by inspectable locations — Outside | VI.3 | 2020-07-31 |
|--------------|---------------------------------|--|------|------------|
| | Title | Added inspectable locations | | |
| | Health and Safety Determination | Revised to "Standard" determination; added standardized description | | |
| | Correction Timeframe | Field added; response input as "Within 30 days" | | |
| | HCV — Correction Timeframe | Field added; response input as "Within 30 days" | | |
| | Rationale | Revised rationale categories, types, and explanations; added standardized codes and descriptions | | |
| | Inspection Process | Revised observation, request for help, action, and more information | | |
| | Tools or Equipment | Field added to deficiency | | |
| Deficiency 2 | | Separated by inspectable locations — Outside | VI.3 | 2020-07-31 |
| | Title | Revised title; added inspectable locations | | |
| | Deficiency Criteria | Revised deficiency criteria | | |
| | Health and Safety Determination | Added standardized description | | |
| | Correction Timeframe | Field added; response input as "Within 30 days" | | |
| | HCV — Correction Timeframe | Field added; response input as "Within 30 days" | | |
| | Rationale | Revised rationale, types, and explanations; added standardized codes and descriptions | | |
| | | | | |